



VELAN CONSTRUCTIONS & HOME DEVELOPERS

RESIDENTIAL BUILDING CONSTRUCTION SPECIFICATION – PREMIUM PACKAGE

Construction Type	Price Per Sq.ft
Solid Blocks	■ 2400 / Sq.ft
Red Bricks	■ 2500 / Sq.ft

SUB STRUCTURE

- Foundation will be of 4' x 4' x 5'.
- R.C.C. Columns up to 1' x 9" size.
- Foundation, Pillars, Columns and Roof reinforced with steel bars.
- Rods – 16mm – 4 Nos.
- Rods – 12mm – 2 Nos.
- Rings – 8mm.
- TMT Brands: PRIME GOLD, TURBOSTEEL, MEENAKSHI TMT, PURVA STRONG, ARS, DURGA TMT, INDIA GOLD or equivalent.
- Lofts, lintels and sunshade reinforced with 8mm or 10mm rods as per structural requirement.
- Foundation refilling and consolidation with excavated earth excess earth will be used for refilling of basement.

BASEMENT

- Plinth beam provided with 1'3" height.
- RR masonry work 1 coarse below ground and 1 coarse above ground level.
- Basement from ground level will be 2.5' height including plinth beam.
- Basement filled with filling earth or mountain earth suited to site condition.
- Anti-termite soil compaction for basement.

SUPER STRUCTURE

- Lintel sunshade at 7' height from floor level.
- Beam size 9" x 6".
- Rods – 10mm – 4 Nos.
- Rings – 8mm – 8" c/c.
- Roof beam and plinth beam size 9" x 9".
- R.C.C roof concrete with 5" thickness using ULTRATECH, ACC, RAMCO or CHETTINADU cement.
- Brick works using chamber branded bricks up to 10 feet height.
- Main and parapet walls – 9" thick.
- Partition walls – 4.5" thick.
- Plastering ratio 1:4 for walls and 1:3 for ceilings.
- Ceiling sponge finish.
- Inner wall sponge finish.
- Outer wall rough finish with sponge.
- ACC, RAMCO PPC or ACC SURAKSHA cement for wall plastering and footing.

DOORS, WINDOWS & VENTILATORS

- GHANA TEAK WOOD main door frame size 3'6" x 7'.
- Main door thickness 1¼" with carving premium design.
- Main door approximate price ■18,500.
- Bedroom frame with MAHOGANY WOOD or SAL WOOD.
- Bedroom plywood pressing doors with exotic style.
- Bathroom and toilet PVC doors overall width 2'6".
- UPVC windows with grill design using 12mm square bars.
- UPVC 3-track sliding windows or openable system.
- Window approximate price ■430/sq.ft.

- Hall window size 5 x 4 & 3 x 4.
- Bedroom window size 3 x 4.
- Kitchen window size 3 x 3.
- Ventilator size 2 x 1'6" with UPVC frames and glass louvers.

DOOR FITTINGS

- All door locks, aldrops and tower bolts in stainless steel.

ELECTRICAL SPECIFICATION

- Electrical wiring with ISI certified wire sizes 1sq, 2.5sq and 4sq.
- Brands: V-Guard, Havells or KEI.
- Concealed wiring system.
- Switches: GM, Hifi & Lisha or equivalent.
- Three phase wiring up to main board only.
- UPS connection included.
- Metal switch boxes provided.

ELECTRICAL POINTS

- All main rooms – 1 ceiling, 4 wall and 2 socket points.
- Other rooms – 1 ceiling and 1 wall point.
- Bathrooms – 1 ceiling point, 1 geyser point and washing machine point.
- Toilet – 1 wall point.
- Hall – TV, Audio system, Telephone, Cable and 4 spot light points.
- Kitchen – Grinder, Refrigerator, Induction stove, Mixie, Exhaust fan and RO point.
- Master bedroom – AC point and two-way switch for fan and light.
- Common area – Calling bell, terrace bulb and ground floor bulb.

PLUMBING

- Main bathrooms with hot and cold taps with shower.
- Geyser provision with solar line.
- EWC White floor mounted Jaquar closet in main bathroom.
- IWC Jaquar closet in common bathroom.

- 1" Ball valve for main water line from overhead tank.
- One tap in ground floor parking and one tap near OHT terrace.
- Waste water drain line connection with 2½" & 4" PVC pipes.
- Supreme / Astral pipes for plumbing.
- Parryware wall mixture / Supreme diverter.
- U clamp for outer plumbing.

FLOORING & WALL TILES

- Vitrified / Ceramic flooring with skirting for all rooms.
- Floor tile budget ■90/sq.ft.
- Bathroom wall tiles up to 10 feet height with ■60/sq.ft budget.
- Bathroom anti-skid floor tiles with ■60/sq.ft budget.
- Kitchen wall tiles up to 7 feet above granite top.
- Parking and portico tiles with ■60/sq.ft budget.
- Extra tile selection cost to be paid by client.

PAINTING SPECIFICATION

- Inner walls – Putty two coats, primer one coat and emulsion two coats.
- Asian Tractor Emulsion or equivalent.
- Outer walls – Primer one coat and Asian Paints Apex two coats.
- Doors – Primer, putty and enamel coating.
- Grill – Primer and enamel coating.
- Main door – Scrapping, touch-up putty, sealer, polish and melamine finish.

CUPBOARD & LOFTS

- Bedroom and kitchen cupboard with Kadapa stone.
- 4 Nos size 4' x 1'3".
- Bedroom loft on one side.
- Kitchen L-type loft 1'9" wide.
- Kitchen granite top with sink.
- Sink options Fiber / SS / Quartz.

MS STEELS

- MS staircase railing in MS pipe/rod around 60kg.
- Safety gate 75kg.
- 1 safety gate per 1000 sqft area.

OTHERS

- Sump 6000 liters extra ■15 per liter.
- Septic tank 6000 liters extra ■15 per liter.
- Overhead tank 1000 liters Supreme / Kaveri / Ganga brand with masonry wall.
- Complementary false ceiling / CCTV worth ■20,000.

NOTE

- Construction will be done according to client floor plan.
- Additional cost difference applicable for Ready Mix Concrete.

EXTRAS

- Borewell and motor.
- Compound wall and gate.
- Foundation height raising.
- Registration.
- Loan expenses.
- Interior wood works.
- Building plan approval.
- Front elevation.
- Rock breaking work if rock found during excavation.

TO BE ARRANGED BY CLIENT

- Temporary EB connection and EB bill.
- Water supply for construction.
- Electrical main board, cable and accessories for temporary / permanent EB.

OPTIONAL TECHNOLOGIES

- AAC Blocks
- Cool Roof Tiles
- Water Softness
- Bio Septic Tank
- Interlock Bricks
- Borewell Recharge
- Rainwater Harvesting
- Steel Doors
- Interlock Mud Bricks
- Gypsum Plastering
- Water Automation

CONTACT DETAILS

- 7010344146 | 8248763380
- velanhomedevelopers@gmail.com
- www.velanconstructions.in
- Hosur, Tamil Nadu

VELAN CONSTRUCTIONS & HOME DEVELOPERS

We Crave Your Dreams