



VELAN CONSTRUCTIONS & HOME DEVELOPERS

RESIDENTIAL BUILDING CONSTRUCTION SPECIFICATION – STANDARD PACKAGE

Construction Type	Price Per Sq.ft
Solid Blocks	■ 2200 / Sq.ft
Red Bricks	■ 2300 / Sq.ft

SUB STRUCTURE

- Foundation will be of 4' x 4' x 5'.
- R.C.C. Columns up to 1' x 9" size.
- Foundation, Pillars, Columns and Roof reinforced with steel bars.
- Rods – 16mm – 4 Nos.
- Rods – 12mm – 2 Nos.
- Rings – 8mm.
- TMT Brands: PRIME GOLD, TURBOSTEEL, MEENAKSHI TMT, PURVA STRONG, SRIRAMA TMT, DURGA TMT or equivalent.
- Lofts, lintels and sunshade reinforced with 8mm or 10mm rods as per structural requirement.
- Foundation refilling and consolidation with excavated earth.

BASEMENT

- Plinth beam provided with 1' height.
- RR masonry work below and above ground level.
- Basement from ground level will be 2' height including plinth beam.
- Basement filled with excess earth from foundation excavation and mountain earth suited to site condition.

SUPER STRUCTURE

- Lintel sunshade at 7' height from floor level.
- Beam size 9" x 6".
- Roof beam and plinth beam size 9" x 9".
- R.C.C. roof concrete with 5" thickness.
- Roof concrete using ULTRATECH, ACC, RAMCO or CHETTINADU cement.
- Brick works using chamber branded bricks up to 10 feet height.
- Main and parapet walls 9" thick.
- Partition walls 4.5" thick.
- Plastering ratio 1:4 for walls and 1:3 for ceilings.
- Ceiling and inner walls sponge finish.
- Outer wall rough sponge finish.

CEMENT BRANDS

- PRIYA
- PENNA
- MAHA
- DALMIA
- VAJRAM
- ULTRATECH
- ACC
- RAMCO
- CHETTINADU

DOORS, WINDOWS & VENTILATORS

- GHANA TEAK WOOD main door frame size 3'6" x 7'.

- Main door thickness 1¼" with premium simple design.
- Main door approximate price ■18,500.
- Bedroom frame with MAGAHONY WOOD or SAL WOOD.
- Bedroom plywood pressing doors with exotic style.
- Bedroom door approximate price ■2300 per door.
- Bathroom and toilet PVC doors overall width 2'6".
- UPVC windows with grill design using 12mm square bars.
- UPVC 3-track sliding windows.
- Window approximate price ■430/sq.ft.
- Hall window size 5 x 4.
- Bedroom window size 3 x 4.
- Kitchen window size 3 x 3.
- Ventilator size 2 x 1'6" with UPVC frames and glass louvers.

DOOR FITTINGS

- Door lock, aldrop and tower bolts in stainless steel.

ELECTRICAL SPECIFICATION

- Concealed electrical wiring with ISI certified wires.
- Wire sizes: 1sq, 2.5sq, 4sq.
- Brands: Kundhan, GM, Finolex, KEI.
- Switches: GM, Hifi & Lisha.
- Three phase wiring up to main board only.
- UPS connection included.
- Metal switch boxes provided.

ELECTRICAL POINTS

- All main rooms: 1 ceiling, 4 wall and 2 socket points.
- Other rooms: 1 ceiling and 1 wall point.
- Bathrooms: 1 ceiling point, 1 geyser point, washing machine point.
- Toilet: 1 wall point.
- Hall: TV, Audio system, Telephone, Cable and 4 spot light points.

- Kitchen: Grinder, Refrigerator, Induction stove, Mixie, Exhaust fan and RO point.
- Master bedroom: AC point and two-way switch for fan and light.
- Common area: Calling bell, terrace bulb and ground floor bulb.

PLUMBING

- Main bathrooms with hot and cold taps and shower.
- Geyser provision in main bathroom.
- EWC Parryware white floor mounted closet in main bathroom.
- IWC in common bathroom.
- 1" ball valve for main water line from overhead tank.
- One tap in parking and one tap in terrace near OHT.
- Drain connection with 2½" and 4" PVC pipes up to septic tank.
- Supreme / Astral pipes.
- Parryware wall mixture / Supreme diverter.
- U clamp for outer plumbing.

FLOORING & WALL TILES

- Vitrified / Ceramic tiles for all rooms.
- Tile budget ■80/sq.ft.
- Bathroom wall tiles up to 7 feet height with ■50/sq.ft budget.
- Bathroom anti-skid floor tiles ■50/sq.ft.
- Kitchen wall tiles 4 feet above granite top.
- Parking and portico tiles ■50/sq.ft.
- Extra tile cost to be paid by client if selected above budget.

PAINTING SPECIFICATION

- Inner walls with putty two coats, primer one coat and emulsion two coats.
- Asian Tractor Emulsion or equivalent.
- Exterior walls with primer one coat and Asian Paints Ace two coats.
- Doors with primer, putty and two coats enamel.
- Grill with primer and enamel coating.
- Main door with scrapping, touch-up putty, sealer, polish and melamine finish.

CUPBOARD & LOFTS

- Bedroom and kitchen cupboard with Kadapa stone.
- 4 Nos size 4' x 1'3".
- Bedroom loft on one side.
- Kitchen L-type loft 1'9" wide.
- Kitchen granite top with sink.
- Sink options Fiber / SS / Quartz.

MS STEELS

- MS staircase railing around 60kg.
- Safety gate 75kg.
- 1 Safety gate per 1000 sqft area.

OTHERS

- Sump 5000 liters extra ■15 per liter.
- Septic tank 5000 liters extra ■15 per liter.
- Overhead tank 1000 liters capacity Supreme / Kaveri / Ganga brand.

NOTE

- Construction will be done according to client floor plan.
- Additional cost difference applicable for Ready Mix Concrete.

EXTRAS

- Borewell and motor.
- Compound wall and gate.
- Front elevation.
- Foundation height raising.
- Registration.
- Loan expenses.
- Interior wood works.
- Building plan approval.

- Rock breaking work if rock found during excavation.

TO BE ARRANGED BY CLIENT

- Temporary EB connection and EB bill.
- Water supply for construction.
- Electrical main board, cable and accessories for temporary / permanent EB.

OPTIONAL TECHNOLOGIES

- AAC Blocks
- Cool Roof Tiles
- Water Softness
- Bio Septic Tank
- Interlock Bricks
- Borewell Recharge
- Rainwater Harvesting
- Steel Doors
- Interlock Mud Bricks
- Gypsum Plastering
- Water Automation

CONTACT DETAILS

- 7010344146 | 8248763380
- velanhomedevelopers@gmail.com
- www.velanconstructions.in
- Hosur, Tamil Nadu

VELAN CONSTRUCTIONS & HOME DEVELOPERS

We Crave Your Dreams